### Fish Creek

# MIDDLE/UPPER FISH CREEK

Estes Valley Watershed

# 2013 Colorado Flood Recovery



COLORADO Colorado Water Conservation Board Department of Natural Resources

#### **Multiple Benefits**

- Protect life, property, and infrastructure
- Educate and engage local community
- Mitigate flood risk
- Increase floodplain capacity
- **Enhance ecosystem** structure & function



Watershed Fish Creek



ocale Larimer County

Local Sponsor



**Estes Valley** Watershed Coalition







**Project Cost** \$1,112,518



**Construction Dates** July 31- Nov. 9. 2017 (102 days)





The

the reach.

The September 2013 flood caused significant changes to the Fish Creek corridor through Estes Park. Fish Creek residences, many of which are located within the active river corridor, sustained extensive damage. During the storm, debris obstructed numerous undersized private culvert crossings and primary resulted in increased damages to the roadway objective of the and private property. Utilities that had been Middle/Upper located in vulnerable areas were also heavily Fish Creek project impacted, including sewer, electric, and was to protect life water lines. and property. This

was accomplished by Following the flood, neighbors rallied removing sediment together to form the Fish Creek Coalition and debris to expand (later formalizing as the Estes Valley floodplain capacity, Watershed Coalition), which worked installing engineered with the Town of Estes Park to create the structures to deflect future Fish Creek Master Plan. The Middle/Upper floods away from critical Fish Creek project area identified in the infrastructure, stabilizing Master Plan was designated by the Natural sediments, and Resources Conservation Service (NRCS) as a promoting improved high priority project, along with several other sediment and debris transport through sections of Fish Creek. This project stemmed from the initial Damage Survey Report developed by the NRCS and Colorado Water Conservation Board (CWCB), which deemed nearly the entirety of Fish Creek in critical need. The Middle/Upper Fish Creek project encompasses four project reaches (Reaches 1, 2, 4, and 5) on Fish Creek.

Destruction of Fish Creek Road as a result of the flood. Photo: Bill Spitz



## Fish Creek Middle & Upper Fish Creek

Denve



1000 ft

# **River Corridor Rehabilitation**

The main components of the Middle/Upper Fish Creek project involved establishing and excavating floodplains, shaping the channel for efficient water and sediment conveyance, and removing flood-deposited sediments. The channel now better accommodates for low, bankfull, and flood stages.

Stabilization of the bank, channel, and floodplain was achieved through bank and roadway embankment protection, bed stabilization, and installation of in-stream structures. Offset protection (buried riprap) was placed near structures in need of protection, and the river was allowed to move and erode its banks in other locations. Floodplain wood, boulder clusters, sills, brush layers, and floodplain roughness elements were installed to slow rapidly moving waters and provide habitat for riparian and aquatic organisms.

Naturalized structures designed to mimic the form and function of beaver dams, also referred to as beaver dam analogs (BDAs), were installed in Reach 4. Beaver dams existed in this reach prior to the flood, and the BDAs were installed to reconnect the channel to the floodplain, raise the groundwater level to support a robust riparian corridor, and benefit aquatic habitat.

Debris, trash, and other flood-deposited materials were removed, and woody material was salvaged and reused where possible. All bare and disturbed areas were seeded and mulched with a native seed mix. Trees, shrubs, and live stakes were planted down to the water's edge. Biodegradable erosion control fabric was used on select slopes to provide erosion control until vegetation is established.

"The Estes Park High School places high value on incorporating community service into our curriculum. Our collaboration with the Estes Valley Watershed Coalition toward the Fish Creek restoration is especially beneficial in this regard. Since the area where the students work is so near the school grounds, our students are frequently reminded of the results of their efforts, and have adopted a sense of ownership for this project."

- Chuck Scott, Estes Park High School Principal



# **Project Objectives**

- Increase floodplain connection by creating floodplain benches and removing floodplain sediment deposits blocking connection
- Stabilize eroding banks
- Improve stream health through installation of habitat features such as riffle-pool structures, in-stream wood, and beaver dam analogs
- Remove flood debris and trash from the riparian corridor
- Re-establish cover on critically eroding land using native riparian vegetation
- Provide bed and bank stability through use of beaver dam analogs and bioengineering techniques

# **Before**

Prior to the 2013 flood, thick willow stands, aspens, beaver meadow complexes, and pine trees were found along Fish Creek. Willows provided excellent habitat for deer, elk, and bears, and were commonly used as elkcalving areas.

Streambank erosion and sedimentation from the flood of 2013 heavily impacted residences, businesses, and critical infrastructure, such as culverts and sewer pipes, along Fish Creek. Sewer services for some area locals were not available for nine months after the flood.

Looking upstream at Reach 5 in 2016 on Fish Creek. Note incised channel with poor floodplain access, eroding banks, and homogenous habitat.

# After

Flood deposited

diment

This project increased overall watershed health and resiliency through sediment removal, floodplain reconnection, grade control via beaver dam analogs, improved in-channel habitat, and revegetation efforts. Fish Creek now has more space to meander and drop sediment prior to entering residential neighborhoods.

Channe

meande

Steep eroded banks

channel

from its floodplain

connected

The community rallied behind the project, producing results above and beyond the outlined project goals. Local citizens contributed to the project through participation in multiple volunteer events, and are eager to continue stream improvements on this and other area reaches.

### REVEGETATION



Reach 5 looking upstream just after construction, featuring a compound channel with improved floodplain access, meanders, in-channel complexity, and soil stabilization through coir logs and erosion control fabric.

sion fabric and coir logs installed to tabilize soils while olants establish

Compound channel with inset low-flow channel and floodplain benche

> In-channel wood nd rock features to nhance complexity



During the post-flood river resiliency master planning process for Fish Creek and Fall River, two river advisory committees were formed to give citizen input to the process. As the master planning process wound down, these two groups joined with parties representing the Upper Big Thompson River and the Black Canyon Creek, forming the Estes Valley Watershed Coalition (EVWC) to implement the Master Plans and secure funding for projects necessary to maintain all four river corridors in a healthy and safe condition for people and wildlife into the future.

By involving a broad representation of stakeholders, EVWC represents diverse interests that work to build participation and acceptance. The EVWC worked to target resources, focusing on manpower and funding, to address important projects identified by the community, such as the Middle/Upper Fish Creek project.

### FOR MORE INFORMATION

Lindsay McFarland, Watershed Coordinator Estes Valley Watershed Coalition EVwatershed@evwatershed.org

www.evwatershed.org www.ColoradoEWP.com

## Partners

**Private landowners Estes Park High School Cross Roads Ministry Estes Park True Value** Home Depot Volunteers for Outdoor Colorado Colorado Water Conservation Board (CWCB) Natural Resources Conservation Service (NRCS)

## Contractors

**TOTAL: \$1,112,518** 

CH2M HILL Engineers, Inc. Otak **Tezak Heavy Equipment Resilient Watershed Partners (RWP)** 

Looking downstream at a newly constructed beaver dam analog structure on Reach 4.



# BUDGET

### **Project Funding by Source**



### **Project Cost Breakdown**



\$100,000 \$200,000 \$300,000 \$400,000 \$500,000